



Test Report: GST18A05-P1J

18W AC-DC High Reliability Industrial Adaptor

■ DESIGN VERIFY TEST

Output Function Test

Input Function Test

Protection Function Test

Component Stress Test

■ SAFETY & E.M.C. TEST

Safety Test

E.M.C. Test

■ RELIABILITY TEST

ENVIRONMENT TEST

DESIGN VERIFY TEST
OUTPUT FUNCTION TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	RIPPLE & NOISE(Max)	V1:80 mVp-p	I/P : 230VAC O/P:FULL LOAD Ta:25°C	V1: 14.2mVp-p	P
2	OUTPUT VOLTAGE(Max) TOLERANCE	V1: 5%~ -5%	I/P: 100VAC~264VAC O/P:FULL~ MIN. LOAD Ta:25°C	V1: -2.71%-0%	P
3	LINE REGULATION (Max)	V1: 1%~ -1%	I/P: 100VAC~ 264VAC O/P:FULL LOAD Ta:25°C	V1: 0%-0%	P
4	LOAD REGULATION(Max)	V1:5%~ -5%	I/P: 230VAC O/P:FULL -MIN LOAD Ta:25°C	V1: -1.37%-1.37%	P
5	SET UP TIME(Max)	230VAC/1000 ms 115VAC/1500 ms	I/P : 230 VAC I/P : 115 VAC O/P : FULL LOAD Ta : 25°C	230VAC/676ms 115VAC / 932ms	P
6	RISE TIME (Max)	230VAC/30 ms 115VAC/30 ms	I/P : 230 VAC I/P : 115 VAC O/P : FULL LOAD Ta : 25°C	230VAC/4.4 ms 115VAC /7 ms	P
7	HOLD UP TIME(Typ)	230VAC/50 ms 115VAC/15 ms	I/P : 230 VAC I/P : 115 VAC O/P : FULL LOAD Ta : 25°C	230VAC/75.2 ms 115VAC /20.8 ms	P
8	OVER/UNDERSHOOT TEST	< ±5%	I/P: 230VAC O/P:FULL LOAD Ta:25°C	<4.6%	P
9	DYNAMIC LOAD	V1: 1000 mVp-p	I/P: 230VAC O/P(1)FULL /Min LOAD 90%DUTY / 1KHZ (2) (1)FULL /Min LOAD 90%DUTY / 3KHZ (3)FULL /Min LOAD 90%DUTY / 5KHZ (4)FULL /Min LOAD 50%DUTY / 120HZ Ta:25°C	382mVp-p 362mVp-p 363mVp-p 420mVp-p	P

INPUT FUNCTION TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	INPUT VOLTAGE RANGE	100VAC~264VAC	I/P:TESTING O/P:FULL LOAD Ta:25°C	73V~264V	P
			I/P: (1)LOW-LINE-3V=97 HIGH-LINE+15%=300 V O/P:FULL/MIN LOAD ON: 30 Sec OFF: 30 Sec 10MIN (2)230Vac ON: 0.5 Sec OFF: 0.5 Sec 20MIN (3)230Vac ON:3Sec OFF:3Sec 12HOURS (POWER ON/OFF NO DAMAGE)	TEST:OK	
2	INPUT FREQUENCY RANGE	47HZ ~63 HZ NO DAMAGE	I/P:100 VAC ~264 VAC O/P:FULL-MIN LOAD Ta:25°C	TEST: OK	P
3	EFFICIENCY(TYP)	81%	I/P:230 VAC I/P:115 VAC O/P:FULL LOAD Ta:25°C	83.246%	P
4	INPUT CURRENT (Typ)	230V/ 0.30A 115V/ 0.50 A	I/P : 230 VAC I/P : 115 VAC O/P : FULL LOAD Ta : 25°C	I =0.22A/ 230VAC I =0.322A/ 115VAC	P
5	INRUSH CURRENT(Typ)	230V/ 65A 115V/35A COLD START	I/P : 230 VAC I/P : 115 VAC O/P : FULL LOAD Ta : 25°C	I =60.7A/ 230VAC I =32.5A/ 115VAC	P
6	LEAKAGE CURRENT	< 0.75 mA / 240 VAC	I/P : 240 VAC O/P : Min LOAD Ta : 25°C	L-FG : 0.013 mA N-FG : 0.013 mA	P
7	NO LOAD CONSUMPTION	< 0.075 W	I/P : 115VAC I/P : 230VAC O/P : NO LOAD Ta : 25°C	< 0.0255 W < 0.0313 W	P

PROTECTION FUNCTION TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	OVER LOAD PROTECTION	110 %~ 150 %	I/P: 230VAC I/P: 115VAC O/P: TESTING Ta:25°C	132.5%/ 230VAC 138.25%/115VAC Hiccup mode, recovers automatically after fault condition is removed	P
2	OVER VOLTAGE PROTECTION	110 ~ 140% rated output voltage Clamp by zener diode	I/P: 230VAC I/P: 115VAC O/P: MIN LOAD Ta:25°C	125.8%/ 230VAC 125.8%/115VAC Clamp by zener diode	P
3	SHORT PROTECTION	SHORT EVERY OUTPUT 1 HOUR NO DAMAGE	I/P: 264VAC O/P: FULL LOAD Ta:25°C	NO DAMAGE Hiccup mode, recovers automatically after fault condition is removed	P

COMPONENT STRESS TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	PWM Transistor (D to S) or (C to E) Peak Voltage	Q 1 Rated 6A/600V	I/P: High-Line +3V =267V AC ON/OFF VDS: O/P: (1) Full Load (2) Output Short (3) Full Load Continue Ta:25°C	(1) 568 V (2) 584V (3) 548V	P
2	Diode Peak Voltage	D100 Rated : 30A/45V	I/P: High-Line +3V =267 V AC ON/OFF O/P: (1) Full Load (2) Output Short (3) Dynamic Load Full Load/ Min. Load 90%Duty/5KHz (4) Dynamic Load 100% Load/ Min. Load 50%Duty/120Hz Ta:25°C	D100 : (1) 38.2V (2) 44.4V (3) 36.6V (4) 43.2V	P
3	Input Capacitor Voltage	C5 Rated: 47u/400V 105°C	I/P: High-Line +3V =267 V O/P: (1) Full Load input on/off (2) Min load input on /Off (3) Full Load /Min load Change Ta:25°C	(1) 384V (2) 386V (3) 380V	P
4	Control IC Voltage Test	PWM IC U1 Rated : 27V 10V(MIN.)	I/P: High-Line +3V =267 V AC ON/OFF O/P: (1) FULL LOAD (2) Output Short (3) O.L.P (4) NO LOAD VR MIN LOW LINE Ta:25°C	(1) 16.7V (2) 17.0V (3) 17.0V (4) 10.9V	P

5	Clamp Diode Peak Voltage	D1 Rated : 2A/800V	I/P : High-Line +3V = 267 V AC ON/OFF O/P : (1) Dynamic Load 90%Duty/1KHz (2) Full load continue Ta : 25°C	(1) 468 V (2) 472 V	P
---	--------------------------	--------------------	---	------------------------	---

SAFETY TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	WITHSTAND VOLTAGE	I/P-O/P: 4.242 KVDC/min I/P-FG: 2.121 KVDC/min	I/P-O/P: 4.666 KVDC/min I/P-FG: 2.545 KVDC/min Ta:25°C	I/P-O/P:1.504mA I/P-FG:1.044mA NO DAMAGE	P
2	ISOLATION RESISTANCE	I/P-O/P:500VDC>100MΩ I/P-FG:500VDC>100MΩ	I/P-O/P: 500 VDC I/P-FG: 500 VDC Ta:25°C	I/P-O/P:9999MΩ I/P-FG:9999MΩ NO DAMAGE	P

E.M.C TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	HARMONIC	EN61000-3-2 CLASS A	I/P:230VAC/50HZ O/P:100%LOAD Ta:25°C	PASS	P
2	CONDUCTION	EN55022 CLASS B	I/P : 230 VAC (50HZ) O/P : FULL/50% LOAD Ta : 25°C	PASS Test by certified Lab	P
3	RADIATION	EN55022 CLASS B	I/P : 230 VAC (50HZ) O/P : FULL LOAD Ta : 25°C	PASS Test by certified Lab	P
4	E.S.D	EN61000-4-2 AIR : 8KV / Contact : 4KV	I/P : 230 VAC/50HZ O/P : FULL LOAD Ta : 25°C	CRITERIA A	P
5	E.F.T	EN61000-4-4 INPUT : 1KV	I/P : 230 VAC/50HZ O/P : FULL LOAD Ta : 25°C	CRITERIA A	P
6	SURGE	EN61000-4-5 Line-Line : 1KV Line-FG : 2KV	I/P : 230 VAC/50HZ O/P : FULL LOAD Ta : 25°C	CRITERIA A	P
7	Test by certified Lab & Test Report Prepare				

RELIABILITY TEST

ENVIRONMENT TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT																																												
1	TEMPERATURE RISE TEST	MODEL : GST18A05-P1J 1. ROOM AMBIENT BURN-IN : 1HRS I/P : 230VAC O/P : FULL LOAD Ta=31.0°C 2. HIGH AMBIENT BURN-IN : 1 HRS I/P : 230VAC O/P : FULL LOAD Ta=56.1°C	<table border="1"> <thead> <tr> <th>NO</th> <th>Position</th> <th>ROOM AMBIENT Ta=31.0°C</th> <th>HIGH AMBIENT Ta=56.1°C</th> </tr> </thead> <tbody> <tr><td>1</td><td>C5</td><td>58.5°C</td><td>82.7°C</td></tr> <tr><td>2</td><td>BD1</td><td>64.3°C</td><td>87.1°C</td></tr> <tr><td>3</td><td>T1</td><td>75.1°C</td><td>98.4°C</td></tr> <tr><td>4</td><td>Q1</td><td>88.7°C</td><td>111.8°C</td></tr> <tr><td>5</td><td>C40</td><td>68.5°C</td><td>91.6°C</td></tr> <tr><td>6</td><td>D1</td><td>71.2°C</td><td>94.7°C</td></tr> <tr><td>7</td><td>C105</td><td>68.5°C</td><td>92.1°C</td></tr> <tr><td>8</td><td>D100</td><td>78.9°C</td><td>101.7°C</td></tr> <tr><td>9</td><td>LF1</td><td>60.1°C</td><td>82.3°C</td></tr> <tr><td>10</td><td>TC</td><td>47.2°C</td><td>74.9°C</td></tr> </tbody> </table>	NO	Position	ROOM AMBIENT Ta=31.0°C	HIGH AMBIENT Ta=56.1°C	1	C5	58.5°C	82.7°C	2	BD1	64.3°C	87.1°C	3	T1	75.1°C	98.4°C	4	Q1	88.7°C	111.8°C	5	C40	68.5°C	91.6°C	6	D1	71.2°C	94.7°C	7	C105	68.5°C	92.1°C	8	D100	78.9°C	101.7°C	9	LF1	60.1°C	82.3°C	10	TC	47.2°C	74.9°C		P
NO	Position	ROOM AMBIENT Ta=31.0°C	HIGH AMBIENT Ta=56.1°C																																														
1	C5	58.5°C	82.7°C																																														
2	BD1	64.3°C	87.1°C																																														
3	T1	75.1°C	98.4°C																																														
4	Q1	88.7°C	111.8°C																																														
5	C40	68.5°C	91.6°C																																														
6	D1	71.2°C	94.7°C																																														
7	C105	68.5°C	92.1°C																																														
8	D100	78.9°C	101.7°C																																														
9	LF1	60.1°C	82.3°C																																														
10	TC	47.2°C	74.9°C																																														
2	OVER LOAD BURN-IN TEST	NO DAMAGE 1 HOUR (MIN)	I/P : 230 VAC O/P : 132% LOAD Ta : 25°C	TEST : OK	P																																												
3	LOW TEMPERATURE TURN ON TEST	TURN ON AFTER 2 HOUR	I/P : 264VAC/100VAC O/P : 100 % LOAD Ta=-30°C	TEST : OK	P																																												
4	HIGH HUMIDITY HIGH TEMPERATURE HIGH VOLTAGE TURN ON TEST	AFTER 12 HOURS IN CHAMBER ON CONTROL 50°C NO DAMAGE	I/P : 272 VAC O/P : FULL LOAD Ta=50°C HUMIDITY= 95 %R.H	TEST : OK	P																																												
5	TEMPERATURE COEFFICIENT	±0.03%/°C (0-50°C)	I/P : 230 VAC O/P : FULL LOAD	±0%/°C (0-50°C)	P																																												
6	STORAGE TEMPERATURE TEST	1. Thermal shock Temperature : -40°C~ +85°C 2. Temperature change rate : 25°C / MIN 3. Dwell time low and high temperature : 30 MIN/EACH 4. Total test cycle : 5 CYCLE 5. Input/Output condition : STATIC		OK	P																																												
7	THERMAL SHOCK TEST	1. Thermal shock Temperature : -30°C~ +70°C 2. Temperature change rate : 25°C / MIN 3. Dwell time low and high temperature : 30 MIN/EACH 4. Total test cycle : 10 CYCLE 5. Input/Output condition : 230VAC/Full Load AC ON/OFF TEST turn on 58sec ; turn off 2sec		OK	P																																												



8	VIBRATION TEST	1 Carton & 1 Set (1) Waveform : Sine Wave (2) Frequency : 10-500Hz (3) Sweep Time : 12in/sweep cycle (4) Acceleration : 2G (5) Test Time : 60min in each axis (X.Y.Z) (6) Ta : 25°C	TEST : OK	P
9	CAPACITOR LIFE CYCLE	SUPPOSE C105 IS THE MOST CRITICAL COMPONENT (1) I/P : 230VAC O/P : FULL LOAD Ta=25°C LIFE TIME (2) I/P : 230VAC O/P : FULL LOAD Ta=50°C LIFE TIME (3) I/P : 230VAC O/P : 75% LOAD Ta=50°C LIFE TIME (4) I/P : 230VAC O/P : 50% LOAD Ta=50°C LIFE TIME	(1) 210662HRS (2) 41291HRS (3) 68966HRS (4) 109814HRS	P
10	MTBF	MIL-HDBK-217F TOTAL FAILURE RATE : 500KHRS		P
11	DMTBF/Accelerated Life Test	Demonstration Mean Time Between Failure (Expected Life): Above 30,000 hours @ TA 50°C		P

TEST RESULT	TESTER	REVIEW	APPROVAL
PASS	FRANK	GESG	WANGDZ

2007/3/20 A50-S014